



NOTICE FOR QUOTE

The City of Pigeon Forge is receiving quotes on the removal and replacement of 1500 square feet of flooring in the community center with Mohawk Ultimate Step vinyl flooring. Specifications may be obtained from the Department of Parks and Recreation office in the Community Center located at 170 Community Center Drive, Pigeon Forge, TN 37863, during the hours of 8:00 and 4:30, Monday through Friday. All questions should be referred to Alan Loy, Building Maintenance Supervisor, at 865-850-4728.

Quotes may be delivered to: 170 Community Center Drive or mailed to:

Department of Parks and Recreation

ATTN: John E. Wilbanks, Director

P.O. Box 605

Pigeon Forge, TN 37868-0605

All quotes will be received until 4:30 p.m. July 22, 2015

The City of Pigeon Forge reserves the right to reject any or all quotes or to accept the quotes most favorable to the City of Pigeon Forge.

It is the policy of the City of Pigeon Forge not to discriminate on the basis of race, color, national origin, age, sex or disability in its hiring and employment practices, or in admission to, or operation of its programs, services and activities. With regard to all aspects of this contract, the agency/program/contractor certifies and warrants it will comply with this policy.

Department of Parks and Recreation

Pigeon Forge, Tennessee

SCOPE OF WORK

Removal and disposal of approximately 1500 square feet of glued down carpet, remove 55 LF of rubber glue down baseboard. Scrape glue and backing. Skim floor. Patch and level areas as needed.

Installation of approximately 1500 square feet of Mohawk Ultimate Step tile, approximately 210 LF of oak ¼" round toe molding stained to match the existing trim and 55 LF of rubber baseboard.

SPECIFICATIONS FOR FLOOR COVERING

The following specifications are minimum acceptable standards. Any deviation from these specifications should be submitted in writing for consideration.

<u>SPECIFICATIONS</u>	<u>YES/NO/ALTERNATE</u>
Mohawk Ultimate Step Wood Grain LVP	_____
Finish Style # C0007	_____
Overall Gauge: 0.1181"	_____
Wear Layer: 20 mil.	_____
Finish: Commercial Grade Urethane	_____
Color: TBD	_____
Installation: Glue down M700 adhesive is preferred	_____
Trim: Oak ¼" round. Color matched to existing trim (Hall Only)	_____

QUOTE SHEET

Return with Quote

Company Name: _____

Address: _____

Contact: _____ Phone: _____

Removal and disposal of existing carpet and installation of new flooring and
1/4" round molding in accordance with the specifications and scope of work

Base Price: \$ _____

Installation Date: _____

Days to Complete: _____

Authorized Signature

Date: _____

Due: 4:30 P.M. WEDNESDAY, JULY 22, 2015