



DEPARTMENT OF PUBLIC WORKS

MARK MILLER
DIRECTOR

NOTICE OF BID

The City of Pigeon Forge is receiving bids on spray applied pipe liner for the Public Works Street Department.

Specifications may be obtained from the Public Works Department at City Hall between the hours of 8:00 a.m. and 4:30 p.m., Monday thru Friday.

Bids will be received until 2:00 p.m., March 12, 2025; at which time they will be opened and read aloud. All bids must be in sealed envelope with bidders name and address on outside and marked "Bid on Pipe Liner."

The City reserves the right to reject any or all bids or to accept the bid most favorable to the City.

This 19th day of February, 2025.

Department of Public Works
City of Pigeon Forge

SPECIFICATIONS

1. Spray Applied Pipe Line of three locations, Eagles Path Way, Garland Street and South River Road.

Eagles Path Way:

Price to include Labor, Material and Equipment to rehab 36" storm drain that crosses diagonally from 814 Kings Hills Blvd across Hickory Dr.

- Build temporary dam and establish bypass pump to keep line dry during installation.
- Clean and prep line to be repaired.
- Remove tree at pipe outlet for access to install liner.
- Establish detour for road closure during installation. Detour will use Osprey Way to access Kings Hills Blvd. Road will be closed for 2 days between 3118 and 3144 Hickory Dr. Road closure is required for staging of equipment and bypass pumping.
- Install ~115' of 36" Ecoliner PVC liner. (Equivalent of what was installed on Old Mill Ave).
- Tear down bypass pump and road closure.
- Clean up work area and demobilize equipment.

Garland Street:

Price to include Labor, Material and Equipment to rehab 48" CMP storm drain that flows from catch basin in intersection of Garland St and N River Rd to West Prong Little Pigeon River.

- Set up temporary pipe plug and bypass pump to keep line dry during installation.
- Clean and prep line to be repaired.
- Spin cast ~105' of 48" CMP ~11' deep with 2" of Mainstay ML-72HP Composite Mortar. (Same mortar used on Old Mill Ave.)
- Touch up any places that need attention and remove bypass pump and temporary pipe plug.
- Clean up work area and demobilize equipment.

South River Road

Price to include Labor, Material and Equipment to camera, locate and uncover junction box in rear entrance to 4061 Parkway. Raise the top of junction box to asphalt elevation and provide permanent access for serviceability. Rehab 24" CMP that flows from hidden junction box to West Prong Little Pigeon River with Ecoliner PVC liner.

- Mobilize camera truck and video inspect 24" storm drain and adjacent drains to pinpoint junction box location.
- Cut asphalt and excavate box to allow access to be raised to asphalt elevation.
- Install risers necessary to accomplish proper elevation and install slotted frame and grate for traffic rated catch basin.
- Clean and prep ~70' of 24" CMP to be rehabilitated.
- Install 24" Ecoliner PVC liner.
- Patch asphalt around catch basin after liner is installed.
- Clean up work area and demobilize equipment.

2. Any questions should be addressed to Duane Rainbolt, 865-453-2757.

BID SHEET

Bidder: _____

Contact: _____

Address: _____

Phone: _____ Fax: _____

Email: _____

Eagles Path Way: _____

Garland Street: _____

South River: _____

TOTAL BID: _____

Time Frame of work: _____